

Hi-Boy Trailer

Standard Features

- 53' deck length
- 8' 6" width
- Main rails – rated at 100,000 lbs load (50 tons)
- Deck height – approximately 57"
- Weight – approximately 12,800 lbs
- Decking – 2" x 6" fir
- Suspension – Holland Air Ride
- L.E.D. lighting
- Sliding axles

Available Options

- Live roll
- Varying deck length from 35' to 53'
- Optional width of 9'
- Tandem axle
- Toolbox
- Decking material



STANDARD FEATURES	
Length	53'
Rating	30 Ton 60,000lbs
Width	8' 6"
Neck Depth	10"
Deck Height	Aprox. 57"
Tare Weight	17,300 lbs (with Apitong Decking)
Coupler Height	50"
King Pin	28"
Coupler Plate	5/16"
Flanges	6" x 1/2" 100 ksi yield
Web	100 ksi yield
Front Bolster	Formed Steel with Four Stake Pockets
Rear Bolster	Formed Steel with Three Stake Pockets
Cross Members	W4x3.2 Steel I-Beams; 16" spacing
Knee Braces	Steel tubing; 48" spacing
Side Rail	C6x8.2 C-Channel
Rub Rail	1/4" x 3"

Stake Pockets	24" Spacing, external, steel
Toolbox	24" x 24" x 36" standard
Floor	1.5" Fir or optional 1 5/16" Apitong
Load Securement	3-Bar Winches, J-Hooks
Mudflaps	Behind rear wheels
Paint	Black (other colours available)
Lighting	SAE J560 7 pin plug at front; 4 pin plug at rear, Grote LED Lights and Sealed wiring harness
King Pin	Holland Weld-in
Landing Gear	Holland Mark V; 2 speed
Suspension	Holland Air Ride – 14" Ride Height, Quickalign
Axles	25,000lbs; Tridem; 60" spread
ABS Brakes	Meritor Wabco, 2S1M
Brake Linings	16 1/2" x 7"
Hubs	Hub piloted 10 stud Unimount; Oil Lubricated
Brake Drums	Cast
Towplate	Standard

We reserve the right to modify, change or revise published specifications without prior notice in order to continually strive for product improvement.